



ROOM NAME	LEGEND	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248																								
201	MEETING SPACE	225	ADV. MANAGERS WORKSPACE	226	STUDIO - HANGING	227	STUDIO	228	STUDIO	229	PROJECT SPACE	230	INFORMAL SPACE	231	FEMALE WC - STUDENTS	232	DISABLED WC - STUDENTS	233	MALE WC - STUDENTS	234	KITCHENETTE / LOUNGE	235	DELETED	236	STUDIO	237	STUDIO	238	STUDIO	239	STUDIO	240	STUDIO	241	STUDIO	242	INFORMAL STUDY SPACE	243	COMMS ROOM	244	STUDIO - CAD	245	COMMS ROOM	246	CAD LAB	247	INFORMAL SPACE	248	INFORMAL SPACE

THIS DRAWING IS AN UNCONTROLLED COPY UNLESS STAMPED OTHERWISE

CONTRACTORS SHALL VERIFY JOB DIMENSIONS BEFORE ANY JOB COMMENCES. ALL SHOP DRAWINGS SHALL BE SUBMITTED TO THE SUPERINTENDENT AND MANUFACTURERS SHALL NOT COMMENCE FROM THE RETURN OF DIMENSIONS DRAWINGS ISSUED BY THE CONSULTANT. DIMENSIONS SHALL TAKE PRECEDENCE OVER SCALES. THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL RELEVANT CONTRACT SPECIFICATIONS AND DRAWINGS COPYRIGHT OF THIS DRAWING IS VESTED IN HANDLE.

General Notes

- (WS XX) INDICATES STUD WALL PARTITION TYPE. REFER TO WALL SYSTEMS SCHEDULE
- (BX XX) INDICATES BLOCKWORK WALL PARTITION TYPE. REFER TO WALL SYSTEMS SCHEDULE
- (GX XX) INDICATES GLAZED WALL PARTITION TYPE. REFER TO WALL SYSTEMS SCHEDULE
- (AX XX) INDICATES AN ACOUSTIC RATED PARTITION. REFER TO ACOUSTIC CONSULTANT REPORT
- (S XX XX) INDICATES A SMOKE SEAL PARTITION. REFER TO WALL SYSTEMS SCHEDULE
- (F XX XX) INDICATES A FIRE RATED PARTITION. REFER TO WALL SYSTEMS SCHEDULE
- (PA21) PAINT FINISH TO WALLS TYPICALLY UNLESS SPECIFIED OTHERWISE
- (SK22) SKIRTING TYPE TYPICALLY UNLESS SPECIFIED OTHERWISE. REFER TO MATERIALS SCHEDULE FOR DESCRIPTION OF SKIRTING TYPES. NO SKIRTING REQUIRED WHERE JOINTS COVER DRY WALL PARTITIONS. NO SKIRTING TO EXPOSED CONCRETE COLUMNS & REINFC. CONCRETE WALLS.
- (XXX) PARTITION SETOUTS DIMENSIONS FROM FINISHED FACE TO FINISHED FACE TYPICALLY
- (+/-) INDICATES A SETOUT POINT
- (AF-XX) ACCESS FLOOR TYPE
- (IA-XX) INSULATION TYPE
- (I) INSTU CONCRETE
- (PC) PRECAST CONCRETE
- (M) BLOCKWORK MASONRY
- (I) INSULATION
- (RF) INDICATES A RECESSED FLOOR BOX
- (AP) INDICATES AN ACCESS PANEL
- (R) REVISION TAG
- (R) REVISION TAG
- (D) DOOR
- (D) ACTUAL LEVEL (e.g. 1.2...)
- (D) DOOR NUMBER
- (D) SUB-DOOR NO. DOOR WITHIN ROOM
- (D) DOOR NO.
- (D) DETAIL NUMBER
- (D) DETAIL CALLOUT
- (D) SHEET REFERENCE NUMBER
- (D) FLOOR WASTE DRAIN

FOR ALL DOOR FINISHES REFER TO DOOR SCHEDULE

STRUCTURAL ADOPTED TO PROVIDE A COORDINATE ADDITIONAL WOODWORK / STRUCTURAL SHEET / STEEL SUPPORTS WITHIN PARTITIONS & WALLS TO ENSURE ADEQUATE SUPPORT & FIXINGS FOR ALL WALL MOUNTED EQUIPMENT E.G. CO. SCREENS & JOINERY.

REFER TO 8000, 8100 & 7100 SERIES

REFER TO 1000 JAM SERIES FOR FACADE SETOUTS AND REFERENCES

REFER TO 8000 PLAN SERIES FOR JOINERY COORDS & 8100 FOR JOINERY DETAILS

REFER TO 7100 SERIES FOR INTERNAL ELEVATIONS

REFER TO 7000 SERIES FOR WALL TYPE DETAILS

REFER TO 7500 SERIES FOR WALL LINING DETAILS

REFER TO 6000 SERIES FOR FINISH DETAILS

FOR FINISHES INFORMATION RELATING TO THE HANGING STUDIO ROOM (208, 214 & 408) REFER TO DRAWING ARS120 - ARS140

FOR FINISHES INFORMATION RELATING TO THE JOSEPH REED FACADE & STUDY SPACE (ROOM 247) REFER TO ARS100 - ARS105

FOR WORKSPACES LISTED BELOW REFER TO DETAIL G3 & 4 DWG 7173 FOR TYPICAL PARTITION TYPES AND FINISHES

BA, 300, 310, 315, 320, 325, 327, 340, 345, 348, 349

REFER TO MATERIALS SCHEDULE FOR SETOUT DETAILS

DIMENSIONS GENERALLY SETOUT TO FACE OF LINING OF WALL TYPE

ALLOW ONE EMERGENCY BUTTON UNLESS NOTED OTHERWISE.

Rev	Issue	Revision Description	Amd	Date
G	SG	UPDATES AS CLOUDED	-	03.03.14
F	SG	UPDATES AS CLOUDED	-	21.02.14
E	SG	FURNITURE REMOVED FROM DRAWING	-	06.02.14
D	SG	UPDATES AS CLOUDED	-	30.01.14
C	SG	DOOR ADDED TO COMMS	-	20.12.13
B	SG	PARTITIONS REMOVED	-	18.11.13
A	SG	SERVICES DOOR SIZE AMENDED	-	11.11.13
15	SG	FLOOR FINISH REVISIONS AS CLOUDED	-	01.05.13
14	SG	000K STAIR LOCATION REVISED	-	28.03.13
13	JC	VALUE MANAGEMENT ISSUE	-	07.09.12
12	JC	100% CD - TENDER ISSUE	-	13.09.12
11	JC	90% CD ISSUE	-	10.08.12
10	JC	75% CD ISSUE	-	13.07.12
09	JC	FINISHES REVISED	-	01.06.12
08	JC	50% CD ISSUE	-	24.04.12
07	JC	FINISHES REVISED	-	20.04.12
06	JC	25% CD ISSUE	-	09.03.12
05	JC	ISSUE FOR COORDINATION	-	

Brookfield MULTIPLEX

NADAAA

NADAAA
1520 Wellington
Street No.2
Boston
Massachusetts
02118 USA

Telephone
+1 817 442 8232
Facsimile
+1 888 442 1417
Email
nadaa@nadaa.com

John Wardle Architects

25 Rokeby Street, Collingwood, Victoria 3066 Australia
Tel : +61 3 8662 0400
www.johnwardlearchitects.com
© 2014 John Wardle Architects ABN 83 006 814 268

Client **University of Melbourne Parkville Campus**

Project **Faculty of Architecture Building and Planning**

Title **GENERAL ARRANGEMENT LEVEL 02 FLOOR PLAN - L02**

Project No. **0913** Scale 1:100 @ A0
Drawing No. **AR1004** Revision **G**
Date May 2011 Drawn - Co-Ord - Check -

FOR CONSTRUCTION